

SIA Workshop Business Continuity Planning

Shrinking the Size and Cost of Back-Up Data Centers

Oct 31, 2006

Copyright 2006 www.naat.com

Network Services Division
North American Access Technologies, Inc.

This workshop will explore how to avoid over-sizing the requirements and costs of a back-up data center, without giving up the flexibility for future growth.

It will cover the challenges, as well as the techniques and solutions to design, locate and budget for a back-up data center in today's constantly changing computing environment.

All in 60 minutes ???

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

In deciding how to best and most cost-effectively, implement a Business Continuity strategy for critical data systems, the Back-Up Data Center is usually the number one item on the list.

*This is usually followed by the next logical question:
“Where should it be located?”*

Then of course:

“How large does it have to be?”

And the last but not least, question:

“How much will it cost?”

Design Goals of Building a Back-up Data Center

1. High Density
2. Flexibility
3. Expandability
4. Infrastructure Redundancy
 - Power & Cooling
 - Back-up Power
5. *Lower Build & Operation Costs*

Back-Up Data Center Basics

- Physical

- Secure Space
- Equipment Racked
- Cabling Organized

- Power

- Normal Utility
- UPS > Battery Back Up (Runtime = 5-60 Minutes)
- Back-Up Generator (Runtime = 1-7 Days >Refuel)

- Environmental

- Precision Cooling
- Humidity Controlled

Copyright 2006 www.naat.com

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

Scaling Ratios

- **Primary Data Center**
 - Support Full User Loads
 - Contains Data for All systems
- **Back-Up Site**
 - Critical Systems Only
 - Support Fraction of User Loads
 - Full Images of Data
 - **Server Count XX% of Primary**

Back-up Site Critical Infrastructure

External Factors

- **Communications**
 - **Data**
 - **Voice**
- **Utility Power**
 - **Back-Up Power**
- **Related Issues**
 - **Habitable Space**
 - **Area Secure**
- **Physical Security**

Most organization's data centers that were designed before 2000 were we built based on technologies did not exist or were not commonplace such as:

- >Bladeservers and 1U Low Profile**
- >Servers w/ Dual Core Processors**
- >VM Virtual Machines**
- >SAN & NAS Storage Arrays**

The result is that these design criterion and performance metrics have radically changed, directly affecting data center design factors such as:

Computing Capability per sq ft (i.e. MPS processing power)

Storage per sq ft (Gigabytes – Terabytes)

Power & Cooling per sq ft (Watts)

Infrastructure Scalability - Designing with the ability to scale up or down with constantly changing systems and demand while maintaining energy efficiency

BCP Options

- **Outsource to Commercial DR Provider**
 - **Lower Upfront Costs**
 - **Higher Long Term Recurring Costs**
- **Use your Organization's Existing Sites**
 - Build Back-up data Center**
 - **Higher Up Front Cost**
 - **Lower Long Term Costs**
- **Hybrid Plan**
 - **Primary - Internal Resources**
 - **Secondary - Outsource**

Back-up Data Center Communications Links

- **T-1 Point-To-Point (P-P)**
- **T-1 (or Fractional) Frame Relay (FR)**
- **Multiple T-1 (N x T-1) (P-P or FR)**
- **T-3 (or Fractional)**
- **Internet Based VPN (T-1 > T-3)**
(Encrypted) IDL
- **Satellite Links**

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

Sample Transmission Data Throughput

Estimated Theoretical Transmission Speeds

Type	MBits/Sec	MBytes/Sec	MB/Min	GB/Hr	10 Hrs	12 Hrs
T-1	1.54	0.19	12	0.695	7	8
T-3	45	6	338	20	203	243
10-Base-FL	10	1	75	5	45	54
100-Base-FX	100	13	750	45	450	540
OC-3	155	19	1,163	70	698	837
1000-Base-LX	1,000	125	7,500	450	4,500	5,400

Note: Actual throughput will be about 75-80% of above due to protocol overhead.

Latency will impact throughput and is not factored in the above.

BCP Geographic Issues

- **Outsource to Commercial DR Provider**
 - **Logistics of Distance to DR Site**
- **Use your Organization's Existing Sites**
(Build Back-up data Center)
 - **Size & Number of Personnel at Alternate Site**
- **Hybrid Plan**
 - **Internal Resources – Primary**
 - **Outsource – Last Resort**

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h 09h 10h 11h 12h 13h 14h 15h 16h 17h 18h 19h 20h

Sample Back-up Data Center Payloads

			Low - Med Density	HI Density
			2U-5U	1U & Blade
Size in Ft.	Sq. Feet	Cabinets	Servers	Servers
18 x 20	360	10-12	60-200	100-500
18 x 30	540	15-20	100-300	150-800
25 x 30	750	25-35	200-600	250-1000+
35 x 30	1000	40-50	300-900	400-2000+
50 x 30	1500	60-70	500-1400	600-3000 +

Sample Back-up Data Center Power

	Low Density 1-2 KVA	Med Density 3-5 KVA	HI Density 6-10 KVA	EXT Density 12-20 KVA+
Cabs	Total KVA			
5	5-10	15-25	30-50	60-100+
8	8-16	24-40	48-80	100-160+
15	15-30	45-75	90-150	180-300+
25	25-50	75-125	150-250	300-500+

Sample Back-up Data Center Cooling

Cooling Requirements

Size in Ft.	Sq. Feet	Cabinets	Low Density	HI Density
			Tons Cool	Tons Cool
10 x 12	120	4-5	1.5-3	3-5
10 x 18	180	6-8	2-5	5-10
18 x 20	360	12-15	10-15	15-25
18 x 30	540	20-25	20-30	25-50

Sample Power & Cooling Requirements

High Density 1 U Servers

1U Servers	Each 1 U Server		U	Rack of 40 Servers		COOLING TONS
	WATTS	BTUs		WATTS	BTUs	
Model			1			
Dell Power Edge 850	345	1,173	1	13,800	46,920	3.9
IBM eServer X306	350	1,190	1	14,000	47,600	4.0
HP Proliant DL360	275	935	1	11,000	37,400	3.1
Sun Fire X2100 Server	300	1,020	1	12,000	40,800	3.4
			1			
Dell Power Edge 1850	550	1,870	1	22,000	74,800	6.2
IBM eServer X336	585	1,989	1	23,400	79,560	6.6
HP Proliant DL360R4	535	1,819	1	21,400	72,760	6.1
Sun Fire X4100 Server	550	1,870	1	22,000	74,800	6.2

Challenge ... *Scotti, I need More Power*

Copyright 2006 www.naat.com

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h 09h 10h 11h 12h 13h 14h 15h 16h 17h 18h 19h

Network Services Division
North American Access Technologies, Inc.

Sample Power & Cooling Requirements

High Density Blade Servers

Blade Servers						COOLING
Model	WATTS	BTUs	U	WATTS	BTUs	TONS
Dell	Rack of 4 Chassis			(40 Blades)		
DELL PowerEdge 1855	5,000	17,000	7U	20,000	68,000	5.7
IBM	Rack of 4 Chassis			(56 Blades)		
IBM BladeCenter=H Class	8,000	27,200	9U	32,000	108,800	9.1
HP	Rack of 5 Chassis			(40 Blades)		
HP BladeSystem p-Class	4,500	15,300	6U	22,500	76,500	6.4
SUN	1 Server			(72Proc)		
Sun Fire E25K Server	25,000	85,000	~	25,000	85,000	7.1
Weber Genesis Silver Barbeque				26,000		2.2



Copyright 2006 www.naat.com

20h 21h 22h 23h 24h 01h 02h 03h 04h

Network Services Division
 North American Access Technologies, Inc.

08h

09h

10h

11h

12h

13h

14h

15h

16h

**Challenge ... Scotti, It's *Very Very Hot* in here
I Need More Cooling**



Heat Load Per Cabinet

**14 Servers@550W =7.5KW
=26,000 BTUs = 1 Weber Grill !!**

**28 Servers@550W =15KW
=52,000 BTUs = 2 Weber Grills !!**

**42 Servers@550W =22.5KW
=78,000 BTUs = 3 Weber Grills !!**

Copyright 2006 www.naat.com

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h 09h 10h 11h 12h 13h 14h 15h 16h 17h 18h 19h

Network Services Division
North American Access Technologies, Inc.



Compact Four-Way
Supremacy is Here

NOW WITH 550 WATTS OF POWER !!!



High Power Density

Watts per Rack ~

2KW-5KW-10KW~+30KW !!!!!

Watts per Sq. Foot ~

100W-150W-200W~+300W!!!!

Challenge...

Scalable UPS Power & COOLING !!

IBM BladeCenter

H Class

9U = 14 Blades

Power=8,000VA

Heat=27,200 Btu/hr

with 4 per 42U rack

=32,000KVA Power

=105,000 Btu/hr

=9 Ton Cooling!!

Copyright 2006 www.naat.com 02h

03h

04h

05h

06h

07h

08h

09h

10h

11h

12h

01h

02h

03h

04h

Network ^{GMT} Services ^{Division}
North American Access Technologies, Inc.



IN-ROW Cooling Technology

VS

Traditional Cooling Technology

High Density Hot-Aisle Containment

Cool Air From Perforated Floor Tiles



Power=150KW 100% Redundant (2N)

Cooling=150KW (N+1) 6 x 30KW

Payload Space=12 Cabinets=504U

Power & Cooling per Cab=12.5KW

Floorspace=17' x 25''=425 Sq. Ft.

No Raised Floor Required

Power=150KW 100% Redundant (2N)

Cooling=80KW (N+1) 3 x 40KW

Payload Space=10 Cabinets=420U

Power per Cab=15.0KW

Cooling per Cabinet Limited to 5KW*

Floorspace=17' x 25''=425 Sq. Ft.

UPS is External for both examples

**Cooling Limited by Airflow*

Copyright 2006 www.naat.com

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h 09h

Network Services Division
North American Access Technologies, Inc.

Flexibility

- Traditional- Fixed Hardwire Electrical Distribution
- + **Modular** – Flexible Power Whips and Plug-in PDUs
- = Easy Reconfiguration for Changing Loads & Equipment Types

Expandability & Growth

- -Pre-build for Maximum (Traditional ~ Maximum Loads)
- + **Modular** = Growth On-Demand

Infrastructure Redundancy

- Power & Cooling
- (N+1) and/or (2 N)



Sample Back-up Data Center Cost Ranges

Sample Data Center Room Size vs Cost Racks & Power

Excluding Cooling System Costs			Low Density	HI Density
Size in Ft.	Sq. Feet	Cabinets	Cost \$K	Cost \$K
10 x 12	120	4-5	10-20	20-40
10 x 18	180	6-8	15-25	25-50
18 x 20	360	12-15	25-40	40-100
18 x 30	540	20-25	50-100	100-250

Sample Data Center Power Costs

KW Hour	Day	Month	Year	5 Years
1	24	720	8,760	43,800

Cost Per KWH	Day	Month	Year	5 Years
\$ 0.10	\$ 2.40	\$ 72.00	\$ 876.00	\$ 4,380.00

Cost Per 100 KWH	Day	Month	Year	5 Years
\$ 10.00	\$ 240.00	\$ 7,200.00	\$ 87,600.00	\$ 438,000.00

Save 5%	\$ 12.00	\$ 360.00	\$ 4,380.00	\$ 21,900.00
----------------	-----------------	------------------	--------------------	---------------------

Sample Data Center Cooling Power Costs

Cost Per 100 KWH	Day	Month	Year	5 Years
\$ 10.00	\$ 240.00	\$ 7,200.00	\$ 87,600.00	\$ 438,000.00

Power Cost for Cooling / percent of Electrical Load=100KW				
% of Load	KW	Month	Year	5 Years
40%	40	\$ 2,880.00	\$ 35,040.00	\$ 175,200.00
60%	60	\$ 4,320.00	\$ 52,560.00	\$ 262,800.00
80%	80	\$ 5,760.00	\$ 70,080.00	\$ 350,400.00

**Systems with Replicated Data
at Multiple Sites**

= High Availability


= *Disaster Avoidance*

= *Business Continuity*

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

IDL

Man-Made Disaster in the Making



• Old Network

- Undocumented
- Cables – Unlabeled & Tangled
- Switch Ports
 - Not Mapped to Drops
- Difficult to Manage

• New Network

- Fully Documented
- Cables Labeled
- Switch Ports
 - Mapped to Drops
- Easy to Manage

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h

06h 07h 08h

Be Prepared..

Data Centers On Demand



20h

04h

05h

06h



Disaster Recovery

Mobile Emergency Datacenter



20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h 09h

Network Services Division
North American Access Technologies, Inc.

Please Consider NAAT Your Business Continuity Source for

- **Consulting Services**
 - Computer and Network Consulting
 - Systems Integration
- **Products**
 - **APC**
 - **HP/Compaq – Cisco - IBM**
 - **Avaya - Mitel**

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

Business Continuity Consulting Services

- Data Center Design
- Project Planning
- Project Management
- Implementation
- Support
- Infrastructure Upgrade

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

Act Now for a Free Site Assessment and receive a Free Attache Case



If your organization consists of 200 or more users or has 10 KVA of individual or combined UPS systems, please call for a Free Site Assessment and you will receive this Expandable Attache Case.

Limit 1 per customer.

Thank you

We hope you have benefited from the information presented here today

**For a copy of this presentation please call
1-800-392-3299 or info@naat.com**

www.naat.com

Copyright 2006 www.naat.com

20h 21h 22h 23h 24h 01h 02h 03h 04h 05h 06h 07h 08h

Network Services Division
North American Access Technologies, Inc.